ABSTRACT.

| Items of work. | Per. | Quantity. | Quantity. |
|---|---|---|---|
| Earthwork excavation and filling in basement ... ... | C. yd. | 408 | 73 |
| Foundation, basement, superstructure, coursed rubble in mortar ... | C. ft. | 15,031 | 2,363 |
| Superstructure, coursed rubble in clay ... ... | „ | ... | 4,721 |
| Arch-work, brick in mortar ... ... ... | „ | 208 | 25 |
| Brick in clay ... ... ... | „ | ... | 217 |
| Coping with brick in mortar ... ... ... | R. ft. | ... | 60 |
| Stone slabs 6″ face dressed for cill and lintel to doors, etc. ... | S. ft. | 1,164 | 30 |
| Do 4½″ do do ... | „ | ... | 105 |
| Plastering with chunam ... ... ... | Sqr. | 133·56 | ... |
| Whitewashing ... ... ... | „ | 74·54 | ... |
| Color washing ... ... ... | „ | 59·02 | ... |
| Pointing with chunam ... ... ... | „ | ... | 81·30 |
| Flooring with Mangalore tiles 8″ square 1″ thick ... | „ | 26·36 | ... |
| Do gravel 6″ deep well rammed ... ... | C. yds | ... | 17 |
| Roofing with Mangalore tiles including reepers and chunam border, pointing, joints with cement. | Sqr. | 49·36 | 12·25 |
| Ridging roof set in cement ... ... ... | R. ft. | 260 | 50½ |
| Wood work, Burma teak wrought and put up ... ... | C. ft. | 495·45 | ... |
| Do honne do do ... ... | „ | ... | 118⅝ |
| Eave boards ... ... ... ... | R. ft. | 481 | 117 |
| Ceiling with pine wood plank ½″ thick ... ... ... | Sqr. | 22·46 | ... |
| Teak wood doors battened 1½″ thick with iron fixture and complete with painting. | S. ft. | 721 | ... |
| Do double do do ... | „ | 72 | ... |
| Do windows, battened and glazed shutter with iron bars. | „ | 286 | ... |
| Do ventilator glazed with iron bars, etc., complete and circular windows in gable | „ | 175 | ... |
| Honne wood doors, windows and ventilators, etc. ... ... | S. ft. | ... | 161½ |
| Zinc gutters to valley 18′ wide ... | R. ft. | 72 | ... |
| Pillars 6 and half pillars 8 of teak wood 9″ × 9″ and 6″ × 9″ and 8′ high, complete. | L. S. | 6 and 8 | ... |
| Wooden or stone pillars to Out Houses 12″ × 6″ × 11′ height of stone. | Each. | ... | 2 |
| Levelling site etc. ... ... ... | Lump sum. | | |
| Finials ... ... ... ... | Each. | 4 | ... |
| Latrine ... ... ... ... | Lump sum. | | |
| Painting to doors, windows and ventilators etc., (chacolate) ... | Sqr. | 27·63 | ... |

S. A. RAMASAMI, *for Executive Engineer.*

## KADUR DIVISION.

*Notice.*

The public is hereby informed that the travellers' bungalow at Belehole in Mudgere Taluk of Kadur District is not available for occupancy.

*Dated 28th November* 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 20th December 1904, for constructing a masonry bridge of 5 arches of 50 feet span across the Bhadra river at Magundy, Koppa Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1906.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two thousand in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a masonry bridge across Bhadra river at Magundy, Koppa Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantities for constructing a masonry bridge of 5 arches of 50 feet span across the Bhadra River at Magundy, Koppa Taluk.

| No. | Items of work. | Per. | Bridge. | Approaches. |
|---|---|---|---|---|
| | | | Quantity | Quantity. |
| 1 | Blasting rock | C. yd. | 209 | ... |
| 2 | Benching rock | C. ft. | 3,768 | ... |
| 3 | Concrete work | L. S. | Rs. | ... |
| 4 | Burnt stone in chunam | C. ft. | 125,179 | ... |
| 5 | Cut stone work | „ | 1,188 | ... |
| 6 | Burnt stone in chunam, roughly dressed | „ | 3,600 | ... |
| 7 | Coping cut stone over parapet | „ | 1,290 | ... |
| 8 | Arch work (ring pins) | „ | 3,713 | ... |
| 9 | Do sheeting | „ | 13,612 | ... |
| 10 | Cornice work in stone (cut stone) | R. ft. | 952 | ... |
| 11 | Cut stone footing | „ | 1,031 | ... |
| 12 | Pointing with chunam | S. yd. | 317·29 | ... |
| 13 | Metalling the road way | C. yd. | 159 | 1,883 |
| 14 | Gravelling | „ | 18 | 209 |
| 15 | Guard stones | Each. | 4 | ... |
| 16 | Baling and diverting water | L. S. | Rs. | ... |
| 17 | Hutting accommodation for maistries and coolies | „ | „ | ... |
| 18 | Centering teakwood work with iron work and straps, etc. | C. ft. | 3,138 | ... |
| 19 | Cast iron drainage pipes for surface drain | R. ft. | 200 | ... |
| 20 | Earth filling between haunches | C. yd. | 847 | ... |
| 21 | Earthwork excavation | „ | 13,860 | ... |
| 22 | Earthfilling | „ | 6,930 | ... |
| 23 | Inscription stone | L. S. | Rs. | ... |
| 24 | Earthwork enbankment for approaches | C. yd. | ... | 15,672 |
| 25 | Do cutting do | „ | ... | 7,432 |
| 26 | Pitching slopes of approach embankment and strengthening wings. | L. S. | ... | Rs. |
| 27 | Turfing | S. yd. | .. | 8,206 |
| 28 | Jungle clearing | L. S. | Rs. | ... |
| 29 | Medical charges | „ | ... | ... |
| 30 | Mile and furlong stones | „ | .. | Rs. |
| 31 | Railway for approaches | „ | ... | „ |
| 32 | Sign post, etc., etc. | „ | ... | „ |
| | Constructing inspection lodge or 3rd class travellers' bungalow including out-houses. | „ | ... | „ |

HARRY J. MOLLOY, *Executive Engineer.*

## BANGALORE CITY MUNICIPALITY.

PROCEEDINGS OF AN ORDINARY MEETING OF THE MUNICIPAL COMMISSIONERS FOR THE CITY OF BANGALORE, HELD AT THEIR OFFICE PREMISES AT 8 A.M., ON THURSDAY THE 3RD NOVEMBER 1904.

*President*—Present.

*Ex-Officio Members.*

*Absent*—The Sr. Surgeon and Sanitary Comr. with the Govt. of Mysore.
*Do*—The Executive Engr., Bangalore Dn.
*Absent*—C. Krishnamurti, Esq.
*Do*—The Principal, Central College.
*Present*—The Amildar, Bangalore Taluk.

*Municipal Commissioners.*

*I—Palace Division.*
*Present*—I. Bronson, Esq.
*Do*—Aga Abdulla Saheb, Esq.

*II—Bale Pete Division.*
*Absent*—B. Gangiah, Esq.
*Present*—D. Venkataramaiya, Esq., B.A.

*III—Manavarte Pete Division.*
*Absent*—Veerabhadra Chetty, Esq.
*Present*—B. K. Garudachar, Esq.

*IV—Alsur Pete Division.*
*Present*—Boppannaiavara Basanna, Esq.
*Do*—N. Ramabhadriah, Esq.

*V—Nagarth Pete Division.*
*Present*—B. V. Ramaswami Chetty, Esq., B.A.
*Absent*—V. Chikkabasanna, Esq.

*VI—Lal-Bagh Division.*
*Present*—J. Cameron, Esq., F.L.S.
*Do*—D. B. Ramachendra Mudaliar, Esq.

*VII—Fort Division.*
*Present*—B. Appajappa, Esq.
*Absent*—A. Somasundra Mudaliar, Esq.

*VIII—Basavangudi Division.*
*Present*—M. K. Krishna Murti Rao, Esq.
*Do*—Khader Mohadeen Meccai, Esq.

*IX—Malleswaram Division.*
*Absent*—S. Venkatarangiengar, Esq.
*Present*—P. R. Subramanya Sastri, Esq., B.A.

1. Read Cash Account Current, Demand, Collection and Balance Statements, Mortuary Return, Progress report of works, Memo of visitors to the Srinivasa Mandiram Library, Statement of materials and Statement of rewards for the destruction of dogs, for September 1904.

*Resolution.*—Passed.